

3.6 kW Solar PV Static Rooftop Mounted Package




HIGHLIGHTS:

- Easy to Setup and Install
- 4 to 6 Day Delivery
- Delivered to Site
- Modular Design
- Mounts Bolt Together
- Encompassing Warranties on Products
- Module Quick Connect
- Full Installation Support
- Full Financing Support

Rumble Energy's solar PV power systems include solar modules, inverters, mounting, ground lugs, fuse box, fusing, combiner box, MC cables, installation, and shipping.

SOLAR MODULES:

The Canadian Solar CSI-CS6P 200 Watt e-Modules operate at 14.1% efficiency, and are accompanied with a 25 year production warranty. (Quantity 18)



ROOFTOP MOUNTING:

The Conergy Suntop rooftop racking system will hold 18 CSI-CS6P 200 Watt solar modules in 2 rows of 9. (Quantity 1)



INVERTER:

The SMA Sunny Boy Grid-Tie 4 KW Inverter comes with a DC Disconnect, and is accompanied with a 10 Year Warranty. (Quantity 1)



Rumble Energy's turnkey (Rumble 3.6 kW-CSI-SM) solar PV power system package has a nameplate rating of 3,600 watts and is composed of the following products:

- Canadian Solar CSI-CS6P 200 Watt e-Modules.
- Conergy Suntop Rooftop Racking System.
- CSA Approved Drop-in Ground Lugs.
- MidNite Combiner Box for 3 150VDC DIN Breakers.
- Outback Fuse Holder for use in PSPV.
- Littlefuse KLKD 600VDC Fuse 1A, 6A, 8A, 10A or 15A.
- SMA Sunny Boy Grid-Tie 4 kW Inverter.

Specifications and descriptions in this document were in effect at the time of publication. Rumble Energy Incorporated reserves the right to change specifications and or product appearance.